

CHITALDRUG DIVISION.

Dated 21st September 1903.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 15th October 1903 for repairing Gangasandra tank Registered No. 126-127 of Holalkere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1904.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M., and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (one hundred) in cash or Government Promissory Notes; as earnest money, and be superscribed "Tender for repairing the Gangasandra tank Registered No. 126 and 127 of Holalkere Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

	Per	Quantity.
Bund—		
Earthwork, ordinary	C. yd.	3,462
Do $\frac{1}{4}$ mile lead	"	995
Earth available from draft cutting only lead	"	2,194
New stone work	"	645
Old stone work	"	100
Re-fixing grade stones	No.	45
Turfing	S. yd.	9,096
Examining and closing the leaks	Lump sum Rs.	
Sluice —		
Earthwork	C. yd.	300
Concrete	C. ft.	395
Burnt brick in surki mortar	Do	853
Arch work	Do	157
Plastering with surki mortar	Sqr.	8-95
Burnt stone slabs	S. ft.	261
Removing and re-fixing gibbet stone	Lump sum Rs.	
Blocking up old sluice	Do	
Old stone revetment	C. yd.	20
Constructing weir 270 feet long—		
Earthwork gravelling soil	C. yd.	2,467
Blasting	Lump sum Rs.	
Brick in surki mortar	C. ft.	2,709
Burnt stone slabs	S. ft.	437
Plastering with surki mortar	Sqr.	25-00
Rough stone work	C. yd.	163
Jelly filling	Do	64
Earthwork-cutting old bund	Do	621
Dismantling old revetment and re-building in the rear of bund.	Lump sum Rs.	

Y. SRINIVASA RAO, Executive Engineer.

Notice dated 21st September 1903.

A sum of Rs. 3-12-0; being the arrears of pay for 15 days in February 1902, due to one badali constable Lakshman Rao, No. 614 of the Jagalur Taluk, who has since been removed from the force and whose whereabouts are not known, is available for payment in the Jagalur Taluk Police office. If the amount is not claimed by the individual or his heirs within six months from this date, it will be credited to Government.

MD. ZAHIRUDDIN MECCAI, Asst. Supt. of Police.